

SITE PLAN NOTES

PROVIDE POSITIVE DRAINAGE AWAY FROM NEW FOUNDATION. (SLOPE FINISH GRADE AWAY MINIMUM 2 % TYPICAL).

IF ANY EARTH WORK AND/OR GRADING IS DONE ON THE PROPERTY OR ANY ACCESS ROADS, OWNER OR CONTRACTOR SHALL MAINTAIN AN UNINTERRUPTED FLOW OF WATER IN SWALES AND NATURAL COURSES. UPON COMPLETION OF THE PROJECT. PROPERTY OWNER IS RESPONSIBLE FOR THE ADEQUACY OF ANY DRAINAGE FACILITIES AND FOR THE CONTINUED MAINTENANCE THEREOF IN A MANNER WHICH WILL PRECLUDE ANY HAZARD TO LIFE, HEALTH, OR DAMAGE TO ADJOINING PROPERTY.

DUCT OPENINGS AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED DURING CONSTRUCTION.

ADHESIVES, SEALANTS AND CAULKS SHALL BE COMPLIANT WITH VOC AND OTHER TOXIC COMPOUND LIMITS.

RECYCLE AND / OR SALVAGE FOR REUSE A MINIMUM OF 50 PERCENT OF THE NONHAZARDOUS CONSTRUCTION AND DEMOLITION WASTE.

POST CONSUMER OR PRE CONSUMER RECYCLED CONTENT VALUE (RCV) MATERIALS ARE USED ON THE PROJECT. TIER 1: NOT LESS THAN A 10 PERCENT RECYCLED CONTENT VALUE.

DUCT OPENINGS AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED DURING CONSTRUCTION.

PAINTS, STAINS AND OTHER COATINGS SHALL BE COMPLIANT WITH VOC LIMITS.

AEROSOL PAINTS AND COATINGS SHALL BE COMPLIANT WITH PRODUCT WEIGHTED MIR LIMITS FOR ROC AND OTHER TOXIC COMPOUNDS.

DOCUMENTATION SHALL BE PROVIDED TO VERIFY THAT COMPLIANT VOC LIMIT FINISH MATERIALS HAVE BEEN USED.

80 PERCENT OF FLOOR AREA RECEIVING RESILIENT FLOORING SHALL COMPLY WITH THE VOC-EMISSION LIMITS DEFINED IN THE COLLABORATIVE FOR HIGH PERFORMANCE SCHOOLS (CHPS), HIGH PERFORMANCE PRODUCTS DATABASE OR BE CERTIFIED UNDER THE RESILIENT FLOOR COVERING INSTITUTE (FRCI) FLOORSCORE PROGRAM; OR MEET CALIFORNIA DEPARTMENT OF PUBLIC HEALTH SPECIFICATION 01350.

MOISTURE CONTENT OF BUILDING MATERIALS USED IN WALL AND FLOOR FRAMING SHALL NOT EXCEED 19% AND SHALL BE CHECKED BEFORE ENCLOSURE.

SPECIAL INSPECTORS EMPLOYED BY THE ENFORCING AGENCY MUST BE QUALIFIED AND ABLE TO DEMONSTRATE COMPETENCE IN THE DISCIPLINE THEY ARE INSPECTING.

VERIFICATION OF COMPLIANCE WITH THIS CODE MAY INCLUDE CONSTRUCTION DOCUMENTS, PLANS, SPECIFICATIONS BUILDER OR INSTALLER CERTIFICATION, INSPECTION REPORTS, OR OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY WHICH SHOW SUBSTANTIAL CONFORMANCE.

PROVIDE CONSTRUCTION WASTE MANAGEMENT PLAN

PER CALGREEN 4.408.2 1. Identify the construction and demolition waste materials to be diverted from disposal by recycling, reuse on the project or salvage for future use or sale. 2. Specify if construction and demolition waste materials will be sorted on-site

(source-separated) or bulk mixed (single stream). 3. Identify diversion facilities where the construction and demolition waste

material will be taken.


4. Identify construction methods employed to reduce the amount of construction and demolition waste generated.

5. Specify that the amount of construction and demolition waste materials diverted shall be calculated by weight or volume, but not by both.

PRIOR TO ANY GRADING, SCRAPING OR TRENCHING WITHIN / UNDER THE CANOPY OF A PROTECTED TREE, A CERTIFIED ARBORIST SHALL BE RETAINED TO PROVIDE SUPERVISION AND RECOMMENDATIONSTO MINIMIZE POSSIBLE DAMAGE TO THE TREE. THE PROPOSED TRENCHING SHALL BE APPROVED BY THE CITY OF SARATOGA PLANNING DEPARTMENT PRIOR TO COMMENCING DIGGING. THE CITY OF SARATOGA ARBORIST IS: KATE BEAR, (408)868-1276


GEOTECHNICAL ENGINEER OR CIVIL ENGINEER SHALL PROVIDE FIELD INSPECTION REPORT IN WRITTING BEFORE REQUESTING CITY INSPECTION OF FOUNDATION.


GEOTECHNICAL ENGINEER OR CIVIL ENGINEER SHALL ISSUE A FINAL REPORT STATING THE COMPLETED PAD, FOUNDATION, FINISH GRADING, AND ASSOCIATED SITE WORK SUBSTANTIALLY CONFORM TO THE APPROVED PLAN, SPECIFICATIONS AND INVESTIGATION.



APN MAP

167-07-034





SITE W/ ROOF PLAN

Juana Briones Elementary School...

N

PROJECT SITE

		ND JONES
SIDENTIAL CODE JILDING CODE UMBING CODE ECHANICAL CODE ECTRIC CODE FOR BUILDING CONSERVATION INERGY CODE NIA GREEN BUILDING STANDARDS CODE E CODE LOCAL AND STATE LAWS AND REGULATIONS	Scope of work • Addition of 568 s.f. to rear and front, consisting of a total of (3) bedrooms, (3) bathrooms, office, living room, dinning room, and kitchen. • New Adu 600 s.f. Above non- living area with addition of 72 s.f. • New Front Porch of 104 s.f. • Upgrade main electrical planel to 400 amps. Stree Data A.p.n. 167-07-034 Lot size 6,133.5 s.f. Fire sprinklers main NO Fire sprinklers addu NO Zoning R-1 Super 15 < 10%	REGINA WALLACE / STEFFOND 4254 SUZANNE DRIVE PALO ALTO, CA. 94306
FLOOR PLAN R PLAN JMB. PLAN N RESIDENCE ER SHEET AILS AILS AILS AILS NDATION MING DETAILS I PLAN I PLAN	(E) LIVING AREA (E) GAME ROOM (E) GAME ROOM (I) S28.0 S.F. (N) LIVING AREA (N) ADU (O) O S.F. (N) PORCH (N) PORCH (N) PORCH (N) PORCH (N) TOTE: NOTE: NEW FIRE SPRINKLERS TO ADU AND MAIN HOUSE WILL BE DIFFERED.	DESIGN BY: PACIFIC BLUE DEVELOPMENTS Michael S Radu 35 Colleen Way Cambell CA. 95008 (408) 504-6826 Cell (408) 504-6826 Cell
NTION PLAN TAMP AREA ght-of-way, which is to be performed by the Developer all subcontractors shall be included within a <u>Single</u> ing Department. uning Permit and payment of all appropriate fees shall mmencement of work, and all work under the permit so incy permit.	<u>Street Opening Permit</u> I be completed	REVISION: A PER CITY COMMENTS DATED 05/08/2024 PACIFICAD
νι	ΣΙΝΙΤΥ ΜΑΡ	SITE W/ ROOF PLAN VICINITY MAP PLAN NOTES
Palo Alto Math Tutoring		DRAWN BY Michael S. Radu

